

ASME B30.5-2007
(Revision of ASME B30.5-2004)

Mobile and Locomotive Cranes

**Safety Standard for Cableways, Cranes, Derricks, Hoists,
Hooks, Jacks, and Slings**

AN AMERICAN NATIONAL STANDARD



**The American Society of
Mechanical Engineers**

Three Park Avenue • New York, NY 10016

CONTENTS

Foreword	v
Committee Roster	vii
B30 Standard Introduction	ix
Summary of Changes	xii
Chapter 5-0 Scope, Definitions, and References	1
Section 5-0.1 Scope of B30.5	1
Section 5-0.2 Definitions	1
Section 5-0.3 References	7
Chapter 5-1 Construction and Characteristics	8
Section 5-1.1 Load Ratings	8
Section 5-1.2 Stability (Backward and Forward)	9
Section 5-1.3 Boom Hoist, Load Hoist, and Telescoping Boom Mechanisms	14
Section 5-1.4 Swing Mechanism	15
Section 5-1.5 Crane Travel	15
Section 5-1.6 Controls	15
Section 5-1.7 Ropes and Reeving Accessories	18
Section 5-1.8 Cabs	19
Section 5-1.9 General Requirements	20
Section 5-1.10 Structural Performance	21
Section 5-1.11 Cranes Used for Other Than Lifting Service	22
Chapter 5-2 Inspection, Testing, and Maintenance	23
Section 5-2.1 Inspection — General	23
Section 5-2.2 Testing	24
Section 5-2.3 Maintenance	25
Section 5-2.4 Rope Inspection, Replacement, and Maintenance	25
Chapter 5-3 Operation	28
Section 5-3.1 Qualifications and Responsibilities	28
Section 5-3.2 Operating Practices	32
Section 5-3.3 Signals	35
Section 5-3.4 Miscellaneous	35
Figures	
1 Commercial Truck-Mounted Crane — Telescoping Boom	1
2 Commercial Truck-Mounted Crane — Nontelelescoping Boom	2
3 Crawler Crane	2
4 Crawler Crane — Telescoping Boom	2
5 Locomotive Crane	3
6 Wheel-Mounted Crane (Multiple Control Stations)	3
7 Wheel-Mounted Crane — Telescoping Boom (Multiple Control Stations)	4
8 Wheel-Mounted Crane (Single Control Station)	4
9 Wheel-Mounted Crane — Telescoping Boom (Single Control Station, Rotating)	4
10 Wheel-Mounted Crane — Telescoping Boom (Single Control Station, Fixed)	5
11 Work Areas	10
12 Telescopic Boom Crane Control Diagram	16
13 Nontelelescopic Boom Crane Control Diagram	17

14	Dead Ending Rope in a Socket	19
15	Core Failure in 19 × 7 Rotation-Resistant Rope	26
16	Examples of Typical Unequal Outrigger Extension Positions	34
17	Standard Hand Signals for Controlling Crane Operations	36
18	Danger Zone for Cranes and Lifted Loads Operating Near Electrical Transmission Lines	39
Tables		
1	Crane Load Ratings	8
2	Required Clearance for Normal Voltage in Operation Near High-Voltage Power Lines and Operation in Transit With No Load and Boom or Mast Lowered	41